



Terminal 30 Paving Seattle, WA

March 2008 Through May 2009

Owner: Port of Seattle

Project Cost: \$2.8 Million

ICON Scope: Paving Sub-Contractor

At Terminal 30 on the South Seattle waterfront, ICON Materials was given the task of turning a parking area and cruise line terminal into a fully functioning seaport container facility. The timing of the project made this a tricky job. The project needed to be completed before the prime cruise line season began, and that meant much of the critical paving sections needed to be completed during the cold, winter months. In addition the 1/2" hot mix asphalt used contained PG70-22 high stress binder. This meant a strong, but much more sticky and difficult hot mix asphalt to work with. The winter weather compounded the difficulty. To combat this, ICON used a Roadtec 2500 MTV to remix the asphalt on site prior to placement to ensure a consistent and high-quality paving and mat finish. In spite of the project's hurdles, the paving was completed on budget and on time.



- 48,000 Yards Hot Mix Asphalt
- 1/2" With PG70-22